



SITE DEVELOPMENT PLANS
PREPARED FOR
NORTHERN PASS TRANSMISSION, LLC
PROPOSED TRANSITION STATION #5
MAIN STREET (US ROUTE 302), BETHLEHEM, NH 03574

OWNER:



ENGINEER:



DRAWING INDEX	
DRAWING	DESCRIPTION
CVR	COVER SHEET
G-001	GENERAL NOTES AND LEGEND
C-100	SITE LAYOUT PLAN
C-101	GRADING PLAN
C-102	EROSION AND SEDIMENTATION CONTROL PLAN
C-103	PLANTING PLAN
C-104	STORMWATER SYSTEM PLAN
C-300	SITE CROSS SECTIONS
C-500	EROSION AND SEDIMENTATION CONTROL NOTES
C-501	EROSION AND SEDIMENTATION CONTROL DETAILS
C-502	EROSION AND SEDIMENTATION CONTROL DETAILS
C-503	CONSTRUCTION DETAILS
C-504	CONSTRUCTION DETAILS
C-505	CONSTRUCTION DETAILS
C-506	CONSTRUCTION DETAILS
C-507	CONSTRUCTION DETAILS
C-508	CONSTRUCTION DETAILS
C-509	CONSTRUCTION DETAILS



NEW HAMPSHIRE STATE LAW REQUIRES HOMEOWNERS AND CONTRACTORS TO CONTACT DIG SAFE, BY DIALING 8-1-1 AT LEAST THREE BUSINESS DAYS BEFORE BEGINNING ANY DIGGING OR EXCAVATION PROJECT. WHEN DIG SAFE RECEIVES A CALL, THE HOMEOWNER OR CONTRACTOR MUST WAIT 72 BUSINESS HOURS. DURING THIS TIME, UTILITY REPRESENTATIVES RESPOND TO MARK THEIR LINES WITHIN YOUR PRE-MARKED AREA. ALL INFORMATION REGARDING DIG SAFE RULES AND REGULATIONS CAN ALSO BE FOUND AT www.digsafe.com.


VICINITY MAP

0 2000' 4000'

SCALE IN FEET

OCTOBER 1, 2015


**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**



This document has been digitally sealed.
Oct 5 2015

\\BMCD\DFS\CLIENTS\TND\NUSC\58466 NPT\DESIGN\SUBSTATION\801-TRANSITION STATION-5A\CADD\NPTT801-CVB.DWG 10/5/2015 9:03 AM KAMARX

NO.	ISSUED FOR PERMITTING	DATE	DRWN	CHKD	APPRV.
1		10/1/15	FP	RLR	BSS
*					*
*					*
*					*
*					*

Transmission
Business

	#
--	---

STATION #3
COVER SHEET
DATE: 10/1/20

SCALE: NTS	
S: LMP	CHK:RLR
W: FP	APR: BSS
WN:	
LTHLEHEM, NH	
TRANSMISSION LINE:	

E NO:
EET 1 OF 18
PTT801-CVR

VISION: XXX

BACKGROUND NOTES:

1.

BACKGROUND INFORMATION TAKEN FROM "EXISTING CONDITIONS PLAN" LL 3140 FOR BETHLEHEM VENTURES, LLC, 1071 MAIN STREET, BETHLEHEM, NH. PREPARED BY CHA, CONSULTING, INC. DATED AUGUST 12, 2015. SURFACE OBSERVABLE INFORMATION SHOWN HEREON IS THE RESULT OF AN ON-THE-GROUND SURVEY PERFORMED BY CHA, CONSULTING INC. IN JULY 2015. A WETLAND IS PRESENT ON THE NORTHERN HALF OF THE SITE BUT WAS NOT FLAGGED DURING THE FIELD SURVEY PERFORMED BY NORMANDEAU.
2.

ELEVATIONS, CONTOURS AND BENCHMARKS ARE BASED ON NAVD 1988 VERTICAL DATUM.
3.

HORIZONTAL LOCATIONS ARE BASED ON NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM NAD 83.
4.

THE SITE IS LOCATED WITHIN ZONE 'X' FLOOD ZONE AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP NUMBER 33009C0136E PANEL 136 OF 1185, GRAFTON COUNTY, NH, DATED FEBRUARY 20, 2008.
5.

PROPERTY AREA = 0.925± ACRES, NPDES/LIMIT OF DISTURBANCE (LOD) AREA TOTAL = 0.884-ACRES (OF WHICH 0.839-ACRES IS ON-SITE AND 0.045-ACRES IS OFF-SITE IN MAIN STREET).

GENERAL NOTES:

1.

GENERAL NOTES SHALL APPLY TO THE SITE DEVELOPMENT PLANS THROUGHOUT. REFER TO INDIVIDUAL SHEETS FOR SHEET SPECIFIC NOTES.
2.

CONTRACTOR(S) TO TAKE AND VERIFY ALL DIMENSIONS AND CONDITIONS OF THE WORK AND BE RESPONSIBLE FOR COORDINATION OF SAME. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO START OF WORK.
3.

ENGINEER ASSUMES NO RESPONSIBILITY AS TO THE CONTENT OF THE EXISTING CONDITIONS PLAN INCLUDING BUT NOT LIMITED TO LOCATION, SIZE, AND ELEVATIONS OF UTILITIES AND STRUCTURES NOT VISIBLE AND WHERE TAKEN FROM PLANS BY OTHERS.
4.

EXISTING CONDITIONS SURVEY INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT "DIGSAFE" PRIOR TO COMMENCEMENT OF WORK AT "811" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS.
5.

THE CONTRACTOR SHALL VERIFY ALL EXISTING SITE AND BUILDING CONDITIONS IN THE FIELD AND CONTACT THE OWNER AND ENGINEER IF THERE ARE ANY QUESTIONS AND/OR CONFLICTS REGARDING THE SITE DEVELOPMENT PLANS AND/OR EXISTING FIELD CONDITIONS PRIOR TO CONSTRUCTION. REFER TO THE PROJECT SPECIFICATIONS MANUAL FOR ADDITIONAL INFORMATION. SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, INFORM THE OWNER AND CONSULT THE CIVIL ENGINEER IMMEDIATELY FOR DIRECTIONS BEFORE PROCEEDING FURTHER WITH WORK IN THIS AREA.
6.

ALL CONSTRUCTION SHALL COMPLY WITH PROJECT SPECIFICATION MANUAL, EVERSOURCE STANDARDS AND SPECIFICATIONS, AND THESE PLANS. IF SPECIFICATIONS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS. INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

a.

NEW HAMPSHIRE STORMWATER MANUAL, VOLUMES 1, 2 & 3, DECEMBER 2008.

b.

NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION MANUAL ON DRAINAGE DESIGN FOR HIGHWAYS, REVISION DATE APRIL 1998.

c.

NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS (2010).

d.

EVERSOURCE BEST MANAGEMENT PRACTICES MANUAL (TO BE FURTHER DEVELOPED).

e.

EVERSOURCE STANDARD SPECIFICATIONS (10-24-2014).
7.

DO NOT INTERRUPT EXISTING SERVICING UTILITIES AND FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER, THE LOCAL MUNICIPALITIES, THE UTILITY PROVIDER, AND ANY APPLICABLE REGULATORY AGENCY. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY SERVICE HAS BEEN PROVIDED.
8.

THE CONTRACTOR SHALL PROVIDE RECORD AS-BUILT DRAWINGS OF ALL CONSTRUCTION IN ACCORDANCE WITH OWNER AND REGULATORY AGENCY REQUIREMENTS (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER AT THE END OF CONSTRUCTION.

9.

WRITTEN DIMENSIONS HAVE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING PLANS. IN CASE OF CONFLICT BETWEEN PLAN SET AND ANY OTHER DRAWING AND/OR SPECIFICATION, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATION.
10.

IF A CONFLICT ARISES BETWEEN PLANS, SPECIFICATIONS, AND/OR DETAILS, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATION.
11.

THE CONTRACTOR SHALL ABIDE BY ALL OSHA, FEDERAL, STATE, AND LOCAL REGULATIONS IN ALL INSTANCES AND WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT POWER COMPANY TO MAKE ARRANGEMENT FOR PROPER SAFEGUARDS. ANY UTILITY COMPANY FEES SHALL BE PAID FOR BY THE CONTRACTOR.
12.

THE ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ENGINEER HAS NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.
13.

ALL NOTES AND DIMENSIONS DESIGNATED "TYPICAL" OR "(TYP.*)" APPLY TO ALL LIKE OR SIMILAR CONDITIONS THROUGHOUT THE PROJECT.
14.

ALTERNATIVE METHODS AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED IF SUBMITTED, REVIEWED, AND APPROVED BY THE OWNER, ENGINEER, AND APPROPRIATE REGULATORY AGENCY PRIOR TO CONSTRUCTION.
15.

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL PRODUCTS AND MATERIALS PER PLANS AND SPECIFICATIONS TO THE OWNER AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ORDERING, FABRICATION, OR DELIVERY TO THE SITE. FOR EACH SUBMITTAL, ALLOW A MINIMUM OF 14 WORKING DAYS FOR REVIEW.
16.

THE CONTRACTOR SHALL RESTORE ANY DRAINAGE STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS OR SIGNAGE AND OTHER INCIDENTAL DISTURBANCES AND DAMAGES DURING CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AS APPROVED BY THE OWNER, ENGINEER AND REGULATORY AGENCY.
17.

THE CONTRACTOR SHALL COMPLY WITH 29 CFR PART 1926 FOR EXCAVATION TRENCHING AND TRENCH PROTECTION REQUIREMENTS.
18.

NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.
19.

DEMOLITION OF EXISTING CONDITIONS INCLUDING BUT NOT LIMITED TO BUILDINGS, STRUCTURES, PAVEMENT, WELLS, SEPTIC, SANITARY SEWER, FENCES, TREES, ETC. SHALL BE PER THE DIRECTION OF EVERSOURCE AND SHALL BE IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.
20.

PERMANENT BENCHMARKS SHALL BE INSTALLED UPON COMPLETION OF CLEARING.
21.

ELECTRICAL SUBSTATION COMPONENTS, UNDERGROUND TRANSMISSION LINES, OVER HEAD TRANSMISSION LINES AND THEIR FOUNDATIONS DEPICTED HEREIN ARE FOR REFERENCE ONLY.
22.

ANY CLEARED AND EXCAVATED MATERIALS WHICH ARE SUSPECTED OF BEING ENVIRONMENTALLY POLLUTED, CONTAMINATED, OR IMPACTED SHALL BE STOCKPILED ON-SITE ON TOP OF POLYETHYLENE SHEETING AND COVERED WITH POLYETHYLENE SHEETING. THE OWNER AND ENGINEER SHALL BE IMMEDIATELY INFORMED UPON ENCOUNTERING THIS MATERIAL. STORAGE, TESTING, TREATMENT, REMOVAL, AND DISPOSAL OF ENVIRONMENTALLY POLLUTED, CONTAMINATED, OR IMPACTED MATERIAL SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.
23.

CONTRACTOR SHALL TAKE PRECAUTIONS TO ENSURE NO DISTURBANCE BEYOND THE DEPICTED LIMIT OF DISTURBANCE.
24.

THE CONTRACTOR SHALL ESTABLISH BEST MANAGEMENT PRACTICES FOR BLASTING OF BEDROCK IN ACCORDANCE WITH THE NHDES PUBLICATION WD-10-12. ROCK BLASTING AND WATER QUALITY MEASURES THAT CAN BE TAKEN TO PROTECT WATER QUALITY AND MITIGATE IMPACTS, 2010. IF THE BLAST ROCK VOLUME GENERATED IS GREATER THAN 5,000 CUBIC YARDS, THE CONTRACTOR SHALL DEVELOP A GROUNDWATER MONITORING PROGRAM FOR SUBMISSION TO THE OWNER AND ENGINEER. BLASTING SHALL NOT COMMENCE UNTIL THESE REQUIREMENTS ARE APPROVED BY THE NHDES, AS REQUIRED.
25.

PROPOSED STORM DRAINAGE SYSTEM SHALL BE HS-20 RATED.

EXISTING LEGEND

	PROPERTY LINE
	ADJOINING PROPERTY LINE
	RIGHT OF WAY LINE
	EASEMENT LINE
	MAJOR CONTOUR
	MINOR CONTOUR
	TREELINE
	OVER HEAD WIRE
	STOCKADE FENCE
	CHAIN LINK FENCE
	WETLANDS LINE
	STREAM OR WATERWAY
	STONEWALL
	WF600-9 WETLAND FLAG
	IP IRON PIPE
	CB/DH CONCRETE BOUND WITH DRILL HOLE
	SB/DH STONE BOUND WITH DRILL HOLE
	SURVEY CONTROL POINT
	UTILITY POLE
	WETLANDS
	BUILDING TO BE DEMOLISHED

LIST OF ABBREVIATIONS


ACP	ASBESTOS CEMENT PIPE	MAX	MAXIMUM
APT	ANGLE POINT	MFR	MANUFACTURER
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	MH	MANHOLE
BIT	BITUMINOUS CONCRETE	MIN	MINIMUM
BLDG	BUILDING	N	NORTHING
BM	BENCH MARK	NO	NUMBER
BW	BOTTOM OF WALL	NOM	NOMINAL
CB	CATCH BASIN	OC	ON CENTER
CATV	CABLE TELEVISION	OCS	OUTLET CONTROL STRUCTURE
CI	CAST IRON PIPE	OD	OUTSIDE DIMENSION
CIC	CAST IRON COVER	PC	POINT OF CURVATURE
CL	CENTERLINE	PED	PEDESTRIAN
CLF	CENTERLINE	POB	POINT OF BEGINNING
CLR	CHAIN LINK FENCE	PIV	POST INDICATOR VALVE
CMP	CORRUGATED METAL PIPE	PRC	POINT OF REVERSE CURVATURE
CO	CLEANOUT	PSI	POUNDS PER SQUARE INCH
CONC	CONCRETE	PT	POINT OF TANGENCY
COR	CORNER	PVC	POLYVINYL CHLORIDE PIPE
CTRS	CENTERS	R	RADIUS
DIA	DIAMETER	RAD	RADIUS
DMH	DRAINAGE MANHOLE	RCP	REINFORCED CONCRETE PIPE
DRIVE	DRIVEWAY	SD	STORM DRAIN
E	EASTING	SDMH	STORM DRAIN MANHOLE
EL	ELEVATION	SESC	SOIL EROSION AND SEDIMENT CONTROL
EMH	ELECTRIC MANHOLE	SS	SANITARY SEWER
EOP	EDGE OF PAVEMENT	SSMH	SANITARY SEWER MANHOLE
EXP	EXPANSION	SSFM	SANITARY SEWER FORCE MAIN
EXIST	EXISTING	SQ FT	SQUARE FOOT
G	GAS	SQ M	SQUARE METER
GALV	GALVANIZED	TYP	TYPICAL
GR	GRATE	TW	TOP OF WALL
HDPE	CORRUGATED HIGH DENSITY POLYETHYLENE PIPE	UC	UNDERGROUND COMMUNICATION
HT	HEIGHT	UD	UNDERDRAIN
INV	INVERT	UE	UNDERGROUND ELECTRICAL
LBS	POUNDS	UP	UTILITY POLE
LF	LINEAR FOOT	VC	VITRIFIED CLAY PIPE
LG	WALL HIGH GRADE	W/O	WITHOUT
LOD	LIMIT OF DISTURBANCE		

PROPOSED LEGEND

	MAJOR CONTOUR
	MINOR CONTOUR
	TREELINE
	PERIMETER FENCE
	GUIDERAIL
	SILT FENCE
	CONSTRUCTION FENCE
	LIMIT OF STONE SURFACING
	LIMIT OF DISTURBANCE
	STORMWATER SWALE
	STORM SEWER PIPE
	STORM INLET
	MANHOLE
	OUTLET CONTROL STRUCTURE
	FLARED END SECTION
	CLEANOUT
	SPOT ELEVATION
	RIP RAP
	STONE SURFACING
	ASPHALT PAVEMENT
	NRCS SOIL TYPE/BOUNDARY

This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION





Grading Layout Point Table				
Point #	Northing	Easting	Elevation	Raw Description
100	649733.77	968827.48	1076.00	BSLOPE
101	649740.47	968829.48	1076.00	BSLOPE
102	649743.84	968835.70	1076.00	BSLOPE
103	649726.13	968895.01	1076.00	BSLOPE
104	649723.64	968896.35	1076.00	BSLOPE
105	649714.06	968893.49	1076.00	BSLOPE
106	649714.35	968902.97	1076.00	BSLOPE
107	649712.68	968908.59	1076.00	BSLOPE
108	649719.38	968910.59	1076.00	BSLOPE
109	649721.06	968904.97	1076.00	BSLOPE
110	649706.37	968919.23	1080.00	TSLOPE
111	649715.95	968922.09	1080.00	TSLOPE
112	649733.37	968912.68	1080.00	TSLOPE
113	649755.73	968837.54	1080.00	TSLOPE
114	649743.91	968817.98	1080.00	TSLOPE

Grading Layout Point Table				
Point #	Northing	Easting	Elevation	Raw Description
115	649745.63	968812.23	1080.00	TSLOPE
116	649761.48	968839.34	1080.00	TSLOPE
117	649739.12	968914.40	1080.00	TSLOPE
118	649704.65	968924.98	1080.00	TSLOPE
119	649714.23	968927.84	1080.00	TSLOPE
120	649729.27	968933.30	1079.50	LOW POINT
121	649737.20	968815.98	1080.00	TSLOPE
122	649738.92	968810.23	1080.00	TSLOPE
123	649758.44	968839.54	1080.00	CL SPILLWAY
124	649756.63	968845.27	1080.00	CL SPILLWAY
125	649766.12	968844.97	1077.00	CL SPILLWAY
126	649752.17	968791.19	1078.00	TSLOPE
127	649764.88	968813.62	0.00	BSLOPE
128	649768.56	968843.76	1076.00	BSLOPE

GRADING PLAN NOTES:

- REFER TO SHEET NPPT802-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
- REFER TO SHEET NPPT803-C100 FOR LOCATIONS OF WALL, PAD AND DRIVEWAY.
- REFER TO SHEET NPPT808-C300 FOR GRADING CROSS SECTIONS.
- NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
- PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATED REFER TO TOP OF FINISH SURFACE.
- ALL FILL AND CUT SLOPES ARE 3-FT HORIZONTAL TO 1-FT VERTICAL (3:1) UNLESS NOTED OTHERWISE.
- CONTRACTOR SHALL PLACE 4" TOPSOIL AND SEED ON ALL CUT AND FILL SLOPES AS SPECIFIED UNLESS ANOTHER SURFACE MATERIAL IS INDICATED. EROSION CONTROL BLANKETS (NORTH AMERICAN GREEN SC250 OR ENGINEER APPROVED EQUAL) SHALL BE PLACED OVER ALL SEEDED SIDE SLOPES.
- AFTER COMPLETION OF YARD SUBGRADE WORK, THE SURFACE COURSE FOR THE SUBSTATION (INSIDE THE FENCE, 3-FT OUTSIDE THE FENCE, AND WHERE INDICATED ON THE PLANS) SHALL CONSISTS OF A 4-INCH LAYER OF CRUSHED BASALT (ANGULAR STONE) STONE MEETING THE GRADATION REQUIREMENTS EXPLAINED IN THE SPECIFICATIONS.
- CONTRACTOR SHALL PROTECT/REPAIR ALL SLOPES UNTIL FINAL VEGETATIVE OR STONE STABILIZATION.
- ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED AND STABILIZED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS.
- STABILIZE ALL DITCHES, SWALES, AND PONDS PRIOR TO DIRECTING STORMWATER RUNOFF TO THEM.
- TURF REINFORCEMENT MAT (TRM) SHALL BE INSTALLED ON ALL 3-FT HORIZONTAL TO 1-FT VERTICAL SLOPES (3:1) OR STEEPER, AND BE NORTH AMERICAN GREEN SC250 OR APPROVED EQUAL.
- EARTHWORK AND COMPACTION SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS MADE IN THE GEOTECHNICAL ENGINEERING REPORT BY OTHERS.



FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

THE NORTHERN PASS

Transmission Business

#

TRANSITION STATION #5
GRADING PLAN

DATE: 10/1/2015
SCALE: 1" = 20'



DES: LMP | CHK: RLR
DRAW: FP | APR: BSS
TOWN: BETHLEHEM, NH
TRANSMISSION LINE:
MILE NO:
SHEET 4 OF 18
NPPT804-C101

REVISION: xxx

SEDIMENT & EROSION CONTROL LEGEND

- CONSTRUCTION FENCE
- EROSION CONTROL BLANKET
- INLET PROTECTION
- SILT FENCE
- STABILIZED CONSTRUCTION ENTRANCE

- NOTES:
- REFER TO SHEET NPTT809-C500 FOR EROSION AND SEDIMENTATION NOTES.
 - TOTAL LIMIT OF DISTURBANCE - 38,518 SF = 0.884 ACRES.




FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

This document has been digitally sealed.
Oct 5 2015

DES: LMP	CHK: RLR	DATE: 10/1/2015
DRW: FP	APR: BSS	
TOWN: BETHLEHEM, NH		
TRANSMISSION LINE:		
MILE NO:		
SHEET 5 OF 18		
NPTT805-C102		
REVISION: XXX		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523
--	---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----



PIPE AND UNDERDRAIN SCHEDULE			
PIPE #	LENGTH (FT)	SLOPE	SIZE
P1	8	0.025	12" HDPE
P2	5	0.040	2" PVC
P3	17	0.044	12" HDPE
P4	13	0.046	8" PVC
P5	6	0.025	12" HDPE
P6	22	0.050	12" RCP
P7	6	0.050	12" RCP

- STORMWATER SYSTEM PLAN NOTES:
- REFER TO SHEET NPTT802-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
 - THIS DRAWING IS INTENDED TO DESCRIBE THE STORMWATER SYSTEM ONLY.
 - NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
 - STORM DRAINAGE SYSTEM CONNECTIONS, MATERIALS, AND METHODS SHALL BE IN ACCORDANCE WITH THE NH DOT STANDARDS AND NH DOT SPECIFICATION SECTIONS 603 AND 604, AS WELL AS OTHER APPLICABLE INDUSTRY CODES AND GOVERNING AGENCY REQUIREMENTS.
 - THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE PROPOSED STORM PIPING WILL CROSS EXISTING UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT THE ENGINEER IN THE EVENT OF ANY DISCOVERED OR UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED SANITARY SEWERS, STORM PIPING AND UTILITIES SO THAT AN APPROPRIATE MODIFICATION MAY BE MADE.
 - MANHOLE RIMS AND CATCH BASIN GRATES SHALL BE SET TO ELEVATIONS SHOWN. SET ALL EXISTING MANHOLE RIMS, GRATES AND OTHER UTILITY TOPS TO BE RAISED OR LOWERED FLUSH WITH FINAL GRADE AS NECESSARY.
 - THE CONTRACTOR SHALL ARRANGE FOR AND COORDINATE WITH APPLICABLE REGULATORY AGENCIES FOR STORM DRAINAGE INSTALLATIONS AND CONNECTIONS.
 - THE CONTRACTOR SHALL COORDINATE WORK TO BE PERFORMED BY THE VARIOUS UTILITY PROVIDERS AND SHALL PAY ALL FEES FOR CONNECTIONS, DISCONNECTIONS, RELOCATIONS, INSPECTIONS, AND DEMOLITION UNLESS OTHERWISE STATED IN THE PROJECT SPECIFICATIONS MANUAL AND/OR GENERAL CONDITIONS OF THE CONTRACT.
 - ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD.
 - ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION FOR APPROVAL PRIOR TO BACKFILLING, IN ACCORDANCE WITH THE APPROPRIATE OWNER, UTILITY PROVIDER, AND APPLICABLE REGULATORY AGENCY REQUIREMENTS.
 - A ONE-FOOT MINIMUM VERTICAL CLEARANCE BETWEEN ELECTRICAL AND TELEPHONE LINES TO STORM PIPING SHALL BE PROVIDED.
 - SITE CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS.
 - THE CONTRACTOR SHALL MAINTAIN ALL FLOWS AND UTILITY CONNECTIONS WITHOUT INTERRUPTION UNLESS/UNTIL AUTHORIZED BY THE OWNER, THE ENGINEER, UTILITY PROVIDERS AND GOVERNING AUTHORITIES.
 - STORM DRAINAGE SHALL BE RATED FOR HS-20 LOADING.
 - UNDERDRAINS MAY BE REQUIRED AS DEEMED NECESSARY BY THE OWNER, GEOTECHNICAL ENGINEER AND/OR ENGINEER BASED ON FINDINGS AFTER EARTHWORK AND EXCAVATION OPERATIONS COMMENCE. PROVIDE MINIMUM 0.5% SLOPE ON ALL UNDERDRAINS. ADDITIONALLY PROVIDE UNDERDRAIN CLEANOUTS AT A MINIMUM OF EVERY 200' OF PIPE OR ONE CLEANOUT PER PIPE RUN WHERE THE PIPE RUN IS LESS THAN 200'.

0 10' 20' 40'
SCALE IN FEET

NORTH


**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

This document has been digitally sealed.
Oct 5 2015

TRANSITION STATION #5
STORMWATER SYSTEM PLAN

DATE: 10/1/2015
SCALE: 1" = 20'


DES: LMP | CHK: RLR
DRW: FP | APR: BSS
TOWN: BETHLEHEM, NH
TRANSMISSION LINE:
MILE NO:
SHEET 7 OF 18
NPTT807-C104
REVISION: XXX




SECTION A-A
SCALE HOR 1" = 20'
VER 1" = 2'

GRADING CROSS SECTION NOTES:

- REFER TO SHEET NPPT802-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
- THIS DRAWING IS INTENDED TO DESCRIBE THE GRADING CROSS SECTIONS ONLY.
- NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
- PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATED REFER TO TOP OF FINISH SURFACE.
- CONTRACTOR SHALL PLACE 4" TOPSOIL AND SEED ON ALL CUT AND FILL SLOPES AS SPECIFIED UNLESS ANOTHER SURFACE MATERIAL IS INDICATED.
- EARTHWORK AND COMPACTION SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS MADE IN THE GEOTECHNICAL ENGINEERING RECOMMENDATIONS REPORT BY OTHERS.
- STRIP AND STOCKPILE EXISTING TOPSOIL IN AREAS OF PROPOSED GRADING AND EARTHWORK.




SECTION B-B
SCALE HOR 1" = 20'
VER 1" = 2'



FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

NO.	REVISION	DATE	DRWN	CHKD	APPRV.
1	ISSUED FOR PERMITTING	10/1/15	FP	BSS	



TRANSITION STATION #5
SITE CROSS SECTIONS

DES: LMP	CHK: RLR
DRW: FP	APR: BSS
TOWN: BETHLEHEM, NH	TRANSMISSION LINE:
MILE NO:	
SHEET 8 OF 18	
NPPT808-C300	

EROSION AND SEDIMENTATION CONTROL GENERAL NOTES:

1. THE SEDIMENT AND EROSION CONTROL PLAN IS ONLY INTENDED TO DESCRIBE THE SEDIMENT AND EROSION CONTROL TREATMENT FOR THIS SITE. SEE SEDIMENT AND EROSION CONTROL DETAILS AND CONSTRUCTION SEQUENCE. REFER TO SITE PLAN FOR GENERAL INFORMATION AND OTHER CONTRACT PLANS FOR APPROPRIATE INFORMATION.

2. CONSTRUCTION ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE GENERAL NOTES, SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING BY THE OWNER, QUALIFIED PROFESSIONAL, AND APPROPRIATE REGULATORY AGENCY PRIOR TO IMPLEMENTATION.

3. THE EROSION AND SEDIMENTATION CONTROL MEASURES, CONSTRUCTION SEQUENCE AND PHASING IS THE MINIMUM RECOMMENDED. THE CONTRACTOR SHALL INSTALL AND MAINTAIN ADDITIONAL MEASURES AND SEQUENCING AS REQUIRED BASED ON ACTUAL FIELD OPERATIONS AND CONDITIONS AND BE CONSISTENT WITH THE NEW HAMPSHIRE STORMWATER MANUAL. SIGNIFICANT ADDITIONS AND/OR MODIFICATIONS FROM THE PLANS SHALL BE SUBMITTED, REVIEWED AND APPROVED BY THE OWNER, QUALIFIED PROFESSIONAL AND APPLICABLE REGULATORY AGENCIES.

4. THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO HELP PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND ADJACENT WETLAND AREA FROM SEDIMENT LADEN SURFACE RUNOFF AND EROSION.

5. APPROPRIATE EROSION/SEDIMENT CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL CLEARING, DEMOLITION AND CONSTRUCTION ACTIVITY WITHIN THE APPROVED LIMITS OF DISTURBANCE. SCHEDULE WORK TO MINIMIZE THE LENGTH OF TIME THAT BARE SOIL WILL BE EXPOSED. CONTRACTOR SHALL ONLY EXCAVATE AS MUCH UTILITY AND STORM PIPE TRENCH WORK AS CAN BE COMPLETED, BACKFILLED AND STABILIZED IN ONE DAY SO AS TO LIMIT THE AMOUNT OF OPEN, DISTURBED TRENCHING. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.

6. THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION/SEDIMENT CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION AND BE IN STRICT CONFORMANCE WITH THE STANDARDS BELOW. THE CONTRACTOR SHALL SUPPLY AND MAINTAIN THESE STANDARDS AND HAVE THEM AVAILABLE ONSITE FOR THE DURATION OF CONSTRUCTION. THE OWNER, AGENTS OF THE REGULATORY AGENCIES AND/OR QUALIFIED PROFESSIONAL SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

A. EVERSOURCE BEST MANAGEMENT PRACTICES MANUAL (TO BE FURTHER DEVELOPED).

B. NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES STORMWATER MANUAL, DECEMBER 2008.

7. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

8. THE CONTRACTOR SHALL KEEP A SUPPLY OF EROSION CONTROL MATERIAL (STRAW BALES, SILT FENCE, JUTE MESH, RIP RAP ETC.) ON-SITE FOR MAINTENANCE AND EMERGENCY REPAIRS.

9. STONE CONSTRUCTION ENTRANCE/EXIT SHALL BE INSTALLED AT START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION. THE LOCATION OF THE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.

10. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE STRAW BALES OR SILT FENCE AROUND THE LIMIT OF PILE. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE THAN 2 MONTHS.

11. COMPLY WITH REQUIREMENTS OF THE EPA FOR NPDES AND RECORD KEEPING.

12. VISUAL SITE INSPECTIONS SHALL BE CONDUCTED WEEKLY, AND AFTER EACH MEASURABLE PRECIPITATION EVENT OF 0.50 INCHES OR GREATER BY QUALIFIED PERSONNEL, TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL, TO ASCERTAIN THAT THE EROSION AND SEDIMENT CONTROL (E&S) BMPS ARE OPERATIONAL AND EFFECTIVE IN PREVENTING POLLUTION. PROVIDE WRITTEN REPORTS IN ACCORDANCE WITH ANY APPLICABLE OWNER, QUALIFIED PROFESSIONAL, AND/OR REGULATORY AGENCY REQUIREMENTS.

13. STOCKPILES OF EARTH MATERIALS SHALL CONFORM TO SOIL STOCKPILE PRACTICES IN SECTION 4.1 OF THE NH DES STORMWATER MANUAL VOLUME 3.

14. DEWATERING SUMP PITS SHALL BE INSTALLED WHEN WATER COLLECTS DURING DURING EXCAVATION TO TRAP AND FILTER WATER FOR PUMPING INTO A SUITABLE DISCHARGE AREA. A PERFORATED VERTICAL STANDPIPE WRAPPED IN NON-WOVEN FILTER FABRIC IS PLACED IN THE CENTER OF THE PIT TO COLLECT FILTERED WATER WHERE IT IS THEN REMOVED FROM THE SUMP PIT IN AN AUTHORIZED MANNER. UNDER NO CIRCUMSTANCES SHALL DEWATERING DRAINAGE BE DISCHARGED INTO A SANITARY SEWER. CONSTRUCTION DEWATERING SHALL CONFORM TO CONSTRUCTION DEWATERING REQUIREMENTS OF THE NH DES STORMWATER MANUAL VOLUME 3 SECTION 4.2.

15. WATER SHALL BE USED FOR DUST CONTROL IN APPROPRIATE AREAS.

16. ALL REGULATORY AGENCY PERMITS REQUIRED FOR THE SITE SHALL BE OBTAINED PRIOR TO SITE WORK COMMENCES.
17. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.
18. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.
19. MAXIMUM SLOPES SHALL NOT EXCEED 3-FT HORIZONTAL TO 1-FT VERTICAL (3:1), UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL VERIFY SLOPE STABILITY OF ALL SLOPES PRIOR TO CONSTRUCTION. UNSTABLE SLOPES SHALL BE LAID BACK (FLATTENED) UNTIL STABLE OR PROVIDE REINFORCING TO ACHIEVE STABILIZATION. SLOPE BENCHES SHALL BE IN ACCORDANCE WITH THE NHDES STORMWATER MANUAL.
20. THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY HIS WORK AT ALL TIMES.
21. TEMPORARY AND PERMANENT SEEDING SHALL SHALL BE IN ACCORDANCE WITH THE PLANTING PLAN, NH DES STORMWATER MANUAL VOLUME 3, AND NH DOT STANDARD SPECIFICATIONS SECTION 644.

ALTERATION OF TERRAIN STANDARD NOTES:

1. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.
2. PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AS NECESSARY PRIOR TO FURTHER EARTH MOVING OPERATIONS. PREVENTION OF EROSION AND SEDIMENT TRANSPORTATION ISSUES WILL BE FACILITATED BY THE PROMPT EMPLOYMENT OF EFFECTIVE TEMPORARY AND PERMANENT CONTROL DEVICES, AS CONDITIONS WARRANT. ADDITIONAL CONTROL DEVICES THAT ARE DETERMINED NECESSARY, NOT OUTLINED HEREIN, MAY BE INSTALLED BY THE OWNER OR OPERATOR.
3. PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE PRIOR TO ROUGH GRADING THE SITE AND OTHER EARTH MOVING ACTIVITIES.
4. DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
5. ROADWAYS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
6. CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
7. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENTATION CONTROL MEASURES WEEKLY AND AFTER EVERY HALF-INCH OF RAINFALL DURING THE LIFE OF THE PROJECT. REMOVE TRAPPED SEDIMENT FROM COLLECTOR DEVICES AS NEEDED.
8. STABLE IS DEFINED AS:

A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED,

B. A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED,

C. A MINIMUM 3-INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED,

D. OR EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
9. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.
10. TEMPORARY AND PERMANENT SEEDING SPECIFICATIONS ARE AS NOTED IN THE "VEGETATION MEASURES" SECTION ON THIS SHEET.
11. STANDARD WINTER NOTES:

A. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

B. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

C. AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3.

WINTER CONSTRUCTION NOTES:

1. WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED AS SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.
2. AN AREA WITHIN 100 FEET OF A PROTECTED NATURAL RESOURCE SHALL BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIER.

3. TEMPORARY MULCH SHALL BE APPLIED WITHIN 7 DAYS OF SOIL EXPOSURE OR PRIOR TO ANY STORM EVENT, BUT AFTER EVERY WORKDAY IN AREAS WITHIN 100 FEET FROM A PROTECTED NATURAL RESOURCE.
4. AREAS THAT HAVE BEEN BROUGHT TO FINAL GRADE SHALL BE PERMANENTLY MULCHED THE SAME DAY.
5. IN THE EVENT OF A SNOWFALL GREATER THAN 1 INCH (FRESH OR CUMULATIVE), THE SNOW SHALL BE REMOVED FROM THE AREAS DUE TO BE SEEDED AND MULCHED.
6. LOAM SHALL BE FREE OF FROZEN CLUMPS BEFORE IT IS APPLIED.
7. A DITCH THAT WILL BE CONSTRUCTED DURING THE WINTER MUST BE STABILIZED WITH RIPRAP.
8. PERMANENT STABILIZATION CONSISTS OF AT LEAST 85% VEGETATION, PAVEMENT/GRAVEL BASE OR RIPRAP.
9. DO NOT EXPOSE SLOPES OR LEAVE SLOPES EXPOSED OVER THE WINTER OR FOR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY PROTECTED WITH MULCH AND EROSION CONTROLS.
10. APPLY STRAW MULCH AT TWICE THE STANDARD RATE (150 LBS. PER 1,000 SF). THE MULCH MUST BE THICK ENOUGH SUCH THAT THE GROUND SURFACE WILL NOT BE VISIBLE AND MUST BE ANCHORED.
11. USE MULCH AND MULCH NETTING OR AN EROSION CONTROL MULCH BLANKET OR MIX FOR ALL SLOPES GREATER THAN 8% OR OTHER AREAS EXPOSED TO DIRECT WIND.
12. INSTALL AN EROSION CONTROL BLANKET IN ALL DRAINAGE WAYS (BOTTOM AND SIDES) WITH A SLOPE GREATER THAN 3%.
13. SEE THE VEGETATION MEASURES FOR MORE INFORMATION ON SEEDING DATES AND TYPES.

CONSTRUCTION SEQUENCE:

- THE FOLLOWING CONSTRUCTION SEQUENCE IS RECOMMENDED (COORDINATE ALL SITE ACTIVITIES AND CONSTRUCTION SEQUENCE WITH THAT OF THE STATION ELECTRICAL EQUIPMENT, OVERHEAD AND UNDERGROUND TRANSMISSION LINES, AND OTHER STATION RELATED CONSTRUCTION):
1. CONTACT THE OWNER, QUALIFIED PROFESSIONAL, AND REGULATORY AGENT AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO COMMENCEMENT OF ANY DEMOLITION, CONSTRUCTION OR REGULATED ACTIVITY ON THIS PROJECT SITE.
2. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE REGULATORY AGENT PRIOR TO THE START OF WORK ON THE SITE. INSTALL PERIMETER EROSION/SEDIMENT CONTROL MEASURES.
3. CONSTRUCT STONE CONSTRUCTION ENTRANCES/EXITS AND INSTALL INLET PROTECTION FOR CATCH BASINS OR INSTALL SILT SACKS ON CATCH BASIN INLETS LOCATED IN OFF-SITE ROADS. INSTALL SILT FENCE AND OTHER EROSION CONTROL DEVICES INDICATED ON THESE PLANS AT PERIMETER OF PROPOSED SITE DISTURBANCE AND INSTALL ALL EROSION/SEDIMENT CONTROL MEASURES AND TREE PROTECTION INDICATED ON THESE PLANS. INSTALL SEDIMENT BASINS AND SEDIMENT TRAPS IF REQUIRED AT LOW AREAS OF SITE OR AS ORDERED BY THE QUALIFIED PROFESSIONAL OR AS SHOWN ON THESE PLANS.
4. CLEAR AND GRUB SITE. STOCKPILE CHIPS. STOCKPILE TOPSOIL. INSTALL EROSION CONTROLS AT STOCKPILES.
5. COMMENCE INSTALLATION OF STORM DRAINAGE SYSTEM.
6. COMMENCE EARTHWORK. CONSTRUCT FILL SLOPE. INSTALL ADDITIONAL EROSION CONTROLS AS WORK PROGRESSES AND CONTINUE STORM DRAINAGE SYSTEM CONSTRUCTION, TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE GRADING.
7. CONSTRUCTION STAKING OF ALL FOUNDATION CORNERS, UTILITIES, ACCESS DRIVES, FENCES AND OTHER SITE APPURTENANCES.
8. ROUGH GRADING AND FILLING OF SUBGRADES AND SLOPES.
9. BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE CONTRACTOR MUST PROVIDE EVIDENCE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE APPROPRIATE REGULATORY AGENCIES AND WHICH IS BEING IMPLEMENTED AND MAINTAINED. THE CONTRACTOR SHALL ALSO NOTIFY THE APPROPRIATE REGULATORY AGENCIES IN WRITING OF ALL RECEIVING SPOIL AND BORROW AREAS WHEN THEY HAVE BEEN IDENTIFIED.
10. CONTINUE INSTALLATION OF STORM DRAINAGE AS SUBGRADE ELEVATIONS ARE ACHIEVED.
11. CONSTRUCT PAD SUBGRADE PREPARATION AND BEGIN FOUNDATION CONSTRUCTION.
12. THROUGHOUT CONSTRUCTION SEQUENCE, REMOVE SEDIMENT FROM BEHIND SILT FENCES, STRAW BALES AND OTHER EROSION CONTROL DEVICES, AND FROM SEDIMENT TRAPS AS REQUIRED. REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL OF 0.50 INCH OR GREATER). INSPECTION OF EROSION/SEDIMENT CONTROL MEASURES SHALL BE ON A WEEKLY BASIS AND AFTER EACH RAINFALL OF 0.50 INCHES OR GREATER. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.

13. COMPLETE GRADING TO SUBGRADES AND COMPLETE CONSTRUCTION OF FOUNDATIONS.
14. CONSTRUCT CURBS, PAVEMENT STRUCTURE AND SIDEWALKS
15. CONDUCT FINE GRADING.
16. PAVING OF ACCESS ROAD
17. CONSTRUCT OFF-SITE ROADWAY IMPROVEMENTS, AS NECESSARY.
18. INSTALL YARD SURFACE STONE. FINAL FINE GRADING OF SLOPE AND NON-PAVED AREAS.
19. PLACE 4" TOPSOIL ON SLOPES AFTER FINAL GRADING IS COMPLETED. FERTILIZE, SEED, AND MULCH.
20. LANDSCAPE INTERIOR NON-PAVED AREAS, NON-GRAVELED AREAS, AND PERIMETER AREAS.
21. INSTALL ON-SITE SIGNAGE AND PAVEMENT MARKINGS
22. CLEAN STORM DRAINAGE PIPE STRUCTURES, DETENTION SYSTEMS AND WATER QUALITY DEVICES OF DEBRIS AND SEDIMENT.
23. UPON DIRECTION OF THE OWNER, QUALIFIED PROFESSIONAL, AND REGULATORY AGENT, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED FOLLOWING STABILIZATION OF THE SITE.

ROUGH GRADING OPERATIONS

1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE GRADING PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.
2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, APPLY MULCH OR STRAW, AND ENCLOSED BY A SILTATION FENCE.

FILLING OPERATIONS

1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE QUALIFIED PROFESSIONAL AND AS SHOWN ON THIS PLAN.


PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND FOUNDATION CONSTRUCTION OPERATIONS

1. SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF EXCAVATIONS, MUD PUMP DISCHARGES, AND UTILITY TRENCH MATERIAL STOCKPILES. STRAW BALES MAY BE USED IF SHOWN ON THE EROSION CONTROL PLANS OR IF DIRECTED BY THE QUALIFIED PROFESSIONAL.
2. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND ANY ROAD OR DRIVEWAY SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.
3. PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE BEEN INSTALLED.
4. AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE OWNER AND THE APPLICABLE REGULATORY AGENCIES.
5. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 85% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.
6. MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY. FILE NOT (NOTICE OF TERMINATION) WITH GOVERNING AUTHORITY RESPONSIBLE FOR REGULATING STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES PER NPDES.

3. PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE BEEN INSTALLED.
4. AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE OWNER AND THE APPLICABLE REGULATORY AGENCIES.

5. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 85% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.

6. MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY. FILE NOT (NOTICE OF TERMINATION) WITH GOVERNING AUTHORITY RESPONSIBLE FOR REGULATING STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES PER NPDES.



This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

THE NORTHERN PASS

TRANSMISSION Business


#

TRANSITION STATION #5
EROSION AND SEDIMENTATION
CONTROL NOTES

SCALE: NTS

DATE: 10/1/2015

DES: LMP | CHK: RLR
DRW: FP | APR: BSS
TOWN: BETHLEHEM, NH
TRANSMISSION LINE:
MILE NO:
SHEET 9 OF 18
NPTT809-C500



PROFILE

PLAN VIEW


CONSTRUCTION ENTRANCE STONE GRADATION	
SIEVE	PERCENT BY WEIGHT PASSING SQUARE MESH SIEVE
2-1/2 INCH	100
2 INCH	90-100
1-1/2 INCH	35-70
1 INCH	0-15
1/2 INCH	0-5

NOTES:

- FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE SURFACE.
- WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN STORM EVENT.

STABILIZED
CONSTRUCTION ENTRANCE
NOT TO SCALE

1
C102




NOTES:


- SILT SOCK SHALL BE FILTREXX™ SILTSOXX™ OR APPROVED EQUIVALENT.
- SEE SPECIFICATIONS FOR SOCK SIZE AND COMPOST FILL REQUIREMENTS.
- SILT SOCK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS, AND REPAIR OR REPLACEMENT SHALL BE PERFORMED AS NEEDED.
- COMPOST MATERIAL SHALL BE DISPERSED ON SITE, AS DETERMINED BY THE QUALIFIED PROFESSIONAL.

SILT SOCK
NOT TO SCALE


4
C102



SIDE VIEW




VIEW LOOKING UPSTREAM



SECTION A

STONE CHECK DAM
NOT TO SCALE

2
C102



PERSPECTIVE VIEW
NOT TO SCALE

NOTES:


- WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES.
- FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER- LAPPED BY SIX INCHES AND FOLDED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.

POSTS: STEEL EITHER "T" OR "U" TYPE OR 2" HARDWOOD.

FENCE: WOVEN WIRE 14 1/2 GA. 6" MAX. MESH OPENING.

FILTER CLOTH: FILTER X, MIRAFI 100X, STABILINKA T140N OR APPROVED EQUAL.


PREFABRICATED UNIT: GEOFAB, ENVIROFENCE, OR APPROVED EQUAL.



SILT FENCE
NOT TO SCALE

3
C102

BLANKET EDGES STAPLED AND OVERLAPPED (4 IN. MIN.)




THE BLANKET SHOULD NOT BE STRETCHED; IT MUST MAINTAIN GOOD SOIL CONTACT

OVERLAP BLANKET ENDS 6 IN. MIN. WITH THE UPSLOPE BLANKET OVERLYING THE DOWNSLOPE BLANKET (SHINGLE STYLE). STAPLE SECURELY.

REFER TO MANUF. RECOMMENDED STAPLING PATTERN FOR STEEPNESS AND LENGTH OF SLOPE BEING BLANKETED


NOTES:

- SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.
- PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.
- SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.
- BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.
- THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.



This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION




Transmission
Business

#

TRANSITION STATION #5
EROSION AND SEDIMENTATION
CONTROL DETAILS

MILE NO:
SHEET 10 OF 18
NPTT810-C501




NOTES:

- FOR LOCATION OF AREAS TO BE PROTECTED SEE SHEET C102.
- SAFETY FENCE SHALL BE FASTENED SECURELY TO THE T-POSTS.
- THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION AND UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.

CONSTRUCTION FENCE
NOT TO SCALE

1
C102




STATION AND ACCESS ROAD SURFACE STONE GRADATION	
SIEVE	PERCENT BY WEIGHT PASSING SQUARE MESH SIEVE
1-1/2 INCH	100
1 INCH	93-100
1/2 INCH	27-58
1/4 INCH	0-8

NOTES:

- REMOVE ALL LOAM, CLAY, MUCK, STUMPS, AND OTHER IMPROPER ROAD FOUNDATION MATERIAL WITHIN 2' OF SUBGRADE. REPLACE WITH COMPACTED GRANULAR FILL MATERIAL ACCEPTABLE TO APPROVING AGENCY. COMPACTION TO BE AT LEAST 95% OF STANDARD PROCTOR.
- STATION SURFACE STONE SHALL EXTEND 3-FT OUTSIDE THE STATION PERIMETER FENCE.
- GRAVEL ACCESS ROADS SHALL HAVE AT LEAST 8-INCHES OF PROCESSED AGGREGATE BASE.

**STATION PAD & ACCESS AREA
GRAVEL SURFACE SECTION**
NOT TO SCALE

3
C100




PAVEMENT AGGREGATE BASE STONE GRADATION	
SIEVE	PERCENT BY WEIGHT PASSING SQUARE MESH SIEVE
2-1/2 INCH	100
2 INCH	95-100
3/4 INCH	50-75
1/4 INCH	25-45
NO. 40	5-20
NO. 100	2-12

ROAD CONSTRUCTION NOTES:

- REMOVE ALL LOAM, CLAY, MUCK, STUMPS, AND OTHER IMPROPER ROAD FOUNDATION MATERIAL WITHIN 2' OF SUBGRADE. REPLACE WITH COMPACTED GRANULAR FILL MATERIAL ACCEPTABLE TO APPROVING AGENCY. COMPACTION TO BE AT LEAST 95% OF STANDARD PROCTOR.
- ALL PAVEMENT, BASE MATERIALS AND WORKMANSHIP TO BE IN COMPLIANCE WITH N.H.D.O.T. "STANDARDS FOR ROAD AND BRIDGE CONSTRUCTION" LATEST EDITION.


**BITUMINOUS CONCRETE
PAVEMENT SECTION**
NOT TO SCALE

4
C100



ELEVATION


NOTE:
ALL END POSTS SHALL HAVE ONE BRACE
ALL CORNER AND INTERMEDIATE BRACE OR
PULL POSTS SHALL HAVE TWO BRACES, WITH
A MAXIMUM SPACING OF BETWEEN POST
ASSEMBLIES OF 500 FEET.



ELEVATION


SECURITY FENCE
NOT TO SCALE

2
C100



FOOTING DETAIL

2
CHAIN LINK FENCE.
FIELD CORE INTO TOP BLOCK.
GROUT FENCE POST IN PLACE.
(AROUND GRAVEL ACCESS AREA)



**RETAINING WALL
WITH REINFORCEMENT**
NOT TO SCALE

5
C104

NOTES:


- ONE DEGREE OR ZERO DEGREE BATTER ANGLE WALLS ARE AVAILABLE USING BLOCKS WITH 7 1/2" (190 MM) OR 6 3/4" (171 MM) KNOBS (SPECIALTY ITEMS).
- ONLY USE STRIPS OF MIRAFI GEOGRID THAT HAVE BEEN FACTORY CUT AND ARE CERTIFIED FOR WIDTH AND STRENGTH BY TENCATE MIRAFI.
- WALL SYSTEM TO BE REDI-ROCK WALL SYSTEM OR APPROVED EQUAL.
- CONTRACTOR SHALL PROVIDE SIGNED AND SEALED DRAWINGS AND DESIGN CALCULATIONS BY A LICENSED ENGINEER IN THE STATE OF NEW HAMPSHIRE PRIOR TO START OF CONSTRUCTION.



This document has been digitally sealed.
Oct 5 2015

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

NO.	REVISION	DATE	BY	CHK	APPV.
1	ISSUED FOR PERMITTING	10/7/15	FP	BSS	



Transmission
Business

TRANSITION STATION #5
CONSTRUCTION DETAILS

DES: LMP CHK:RLR
DRW: FP APR: BSS








TOWN:
BETHLEHEM, NH

TRANSMISSION LINE:


MILE NO:
SHEET 12 OF 18

NPTT812-C503

REVISION: XXX



- NOTES:**
- 25'-0" RAIL PANELS MAY BE USED IN PLACE OF 12'-6" PANELS, EXCEPT ON CURVES WITH A RAIL RADIUS OF LESS THAN 300 FT.
 - GUIDERAIL HEIGHT SHALL BE SET FROM THE GRADE AT THE FACE OF RAIL.
 - DESIGNATIONS PROVIDED IN BRACKETS [] REFERENCE STANDARD ELEMENTS DETAILED IN "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE", LATEST ADOPTED VERSION, AASHTO-AGC-ARTBA JOINT COOPERATIVE COMMITTEE.
 - SEE STD. NO. DL-1 FOR BEAM GUIDERAIL DELINEATORS.
 - PAID FOR UNDER APPROPRIATE 606 ITEMS, OR AS SHOWN ON PLANS.
 - DIMENSIONS OF PLASTIC AND SYNTHETIC BLOCKOUTS ARE AS SHOWN ON MANUFACTURER'S DRAWINGS.
 - POSTS SHORTER THAN THE 7'-0" INDICATED ON THE DETAIL, BUT NOT LESS THAN 6'-6", MAY ONLY BE USED WHEN
 - THE SLOPE BEHIND THE GUIDERAIL IS NO STEEPER THAN 4:1
 - WHERE THE DISTANCE FROM THE BACK OF THE POST TO THE BREAK OF THE SLOPE IS A MINIMUM OF 2'-0"
 - AND THEN ONLY AS APPROVED OR SPECIFICALLY SHOWN ON THE PLANS.




SOURCE: NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION.
NOTE: NHDOT GUIDERAIL DETAILS SHOWN FOR REFERENCE ONLY.

NHDOT GUIDERAIL (GR-14)
NOT TO SCALE

This document has been digitally sealed.
Oct 5 2015

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

NO.	DATE	BY	CHK	APPV.
1	10/7/15	FP	BSS	
		DATE	DATE	





Transmission
Business

TRANSITION STATION #5
CONSTRUCTION DETAILS

MILE NO:
SHEET 13 OF 18
NPTT813-C504


DIAMETER	WALL THICKNESS (MIN.)	FLOOR THICKNESS (MIN.)
4'	5"	6"
5'	6"	8"
6'	7"	8"
8'	9"	10"

CORE HOLE SIZE				
PIPE SIZE	RCP CORE HOLE DIA.		PLASTIC CORE HOLE DIA.	
INCHES	INCHES	FEET	INCHES	FEET
6			7	0.6
12	18	1.5	18	1.5
15	22	1.8	20	1.7
18	26	2.2	24	2.0
24	34	2.8	32	2.7
30	42	3.5	42	3.5
36	48	4.0	48	4.0
42	54	4.5	54	4.5
48	64	5.3	64	5.3
54	72	6.0		
60	78	6.5		




NOTE:
No. 4 REBAR ENCASED IN CORROSION RESISTANT RUBBER OR OTHER MATERIAL APPROVED BY THE OWNER'S REPRESENTATIVE.

MANHOLE STEP
NOT TO SCALE




- NOTES:
- ALL DIMENSIONS ARE NOMINAL.
 - LABEL TYPE OF MANHOLE WITH 3" HIGH LETTERS IN THE CENTER OF THE COVER.




SOURCE: NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION
STANDARD PLANS FOR ROAD CONSTRUCTION 2010.

MANHOLE FRAME AND COVER
NOT TO SCALE




- NOTES:
- ALL DIMENSIONS ARE NOMINAL.
 - NOT TO BE USED WHEN BICYCLE TRAFFIC IS ANTICIPATED.
 - USE 3-FLANGE FRAME IF INSTALLED ADJACENT TO GRANITE CURB.
 - FREE OPEN AREA = 1.80 S.F.






SOURCE: NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION
STANDARD PLANS FOR ROAD CONSTRUCTION 2010.

TYPE "E" GRATE
NOT TO SCALE




This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION




SECTION B-B
FLAT SLAB TOP

- GENERAL NOTES:
- STRUCTURE TO CONFORM TO NH DOT SECTION 604 REQUIREMENTS.
 - FITTING FRAME TO GRADE MAY BE DONE WITH PREFABRICATED ADJUSTMENT RINGS OR CLAY BRICKS (2 COURSES MAX.).
 - CONE SECTIONS MAY BE EITHER CONCENTRIC OR ECCENTRIC, OR FLAT SLAB TOPS MAY BE USED WHERE PIPE WOULD OTHERWISE ENTER INTO THE CONE SECTION OF THE STRUCTURE AND WHERE PERMITTED.
 - PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
 - FOR STRUCTURES WITH DIAMETERS GREATER THAN 4', THE DIAMETER MAY BE CONSTANT FROM TOP TO BOTTOM WITH A FLAT SLAB TOP, OR A RISER SECTION THAT TRANSITIONS FROM A STANDARD 4' CONE SECTION TO THE LARGER DIAMETER RISER OR BASE SECTION MAY BE USED.
 - OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
 - PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
 - ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN 75% OF A HORIZONTAL CROSS-SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS.
 - DEEP SUMP CATCH BASIN SHALL HAVE A MINIMUM OF 4' SUMP.





SOURCE: NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION
STANDARD PLANS FOR ROAD CONSTRUCTION 2010.

PRECAST CONCRETE
MANHOLE AND CATCH BASIN
NOT TO SCALE



PIPE DIA.	A	B	H	L	W
12"	6.5"	10.0"	6.5"	25'	29"




NOTES:

- FLARED END SECTION SHALL BE HIGH DENSITY POLYETHYLENE MEETING ASTM D3350 MINIMUM CELL CLASSIFICATION 213320C.
- METAL THREADED FASTENING ROD SHALL BE STAINLESS STEEL.
- INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURERS INSTALLATION INSTRUCTIONS


END SECTION FOR HDPE PIPE
NOT TO SCALE

1
C104




PIPE TRENCH
NOT TO SCALE

3
C104




NOTES:

- THE SUBGRADE FOR GEOTEXTILE FABRIC AND RIP-RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN.
- THE ROCK USED FOR RIP-RAP SHALL CONFORM TO NHDOT CLASS C STONE.
- GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP-RAP. DAMAGED AREAS IN THE FABRIC SHALL BE PREPARED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- STONE FOR THE RIP-RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.



OUTLET PROTECTION
NOT TO SCALE


2
C104



NOTES:

- DESIGN OF END SECTION SHALL CONFORM TO STANDARD REINFORCED CONCRETE PIPE.
- CUT OFF WALL TO BE POURED IN FIELD, IF NECESSARY, AS DIRECTED BY THE ENGINEER.
- PAYMENT FOR THE CUT OFF WALL WILL BE MADE UNDER THE APPROPRIATE CONTRACT ITEMS.
- PROVIDE ANIMAL BARRIER ON OUTLET. BARRIER SHALL NOT RESTRICT STORMWATER FLOW.

ITEM NO.	PIPE DIA.	APPROX. SLOPE X to Y	A	B	C	D	R	T
603.30112	12"	3 TO 1	4"	24"	48 7/8"	24"	9"	2"




SOURCE: NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION
STANDARD PLANS FOR ROAD CONSTRUCTION 2010.

CONCRETE END SECTION FOR
REINFORCED CONCRETE PIPE
NOT TO SCALE

4
C104

This document has been digitally sealed.
Oct 5 2015

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**



RETAINING WALL (INSIDE FACE)

3' (MIN)

2'

12" THICK, REINFORCED CONCRETE CUTOFF WALL

12" (MIN)

#5 BARS

RIPRAP SPILLWAY (SEE DETAIL 1)

SECTION B-B




1. GEOTEXTILE PLACEMENT: THE GEOTEXTILE SHALL BE PLACED ON A SMOOTH GRADED SURFACE APPROVED BY THE ENGINEER. THE GEOTEXTILE SHALL BE PLACED IN SUCH A MANNER THAT IT WILL NOT EXCESSIVELY STRETCH OR TEAR UPON PLACEMENT OF THE OVERLYING MATERIALS. CARE SHALL BE TAKEN TO PLACE THE GEOTEXTILE IN INTIMATE CONTACT WITH THE SOIL SUCH THAT NO VOID SPACES EXIST BETWEEN THE UNDERLYING SOIL AND THE GEOTEXTILE. ANCHORING OF THE GEOTEXTILE SHALL BE ACCOMPLISHED THROUGH THE USE OF KEY TRENCHES OR APRONS AT THE CREST AND TOE OF SLOPE.
2. GEOTEXTILE SHEETS SHALL BE JOINED BY EITHER SEWING OR OVERLAPPING. ALL OVERLAPS AND SEAMS SHALL BE SUBJECT TO THE APPROVAL OF THE ENGINEER. OVERLAPPED SHEETS SHALL HAVE A MINIMUM OVERLAP OF 18 IN. EXCEPT WHERE PLACED UNDERWATER WHERE THE OVERLAP SHALL BE A MINIMUM OF 3 FT. OVERLAPS SHALL BE CONSTRUCTED WITH THE UPSTREAM SHEET PLACED OVER THE DOWNSTREAM SHEET OR THE UPSLOPE SHEET PLACED OVER THE DOWNSLOPE SHEET. ALL OVERLAPS SHALL BE PINNED ON 3 FT. CENTERS TO HOLD THE OVERLAP IN PLACE DURING STONE PLACEMENT. PINS ARE RECOMMENDED TO BE 3/16 IN. DIAMETER, 18 IN. LONG STEEL PINS POINTED AT ONE END, AND FITTED WITH A 1.5 IN. DIAMETER WASHER AT THE OTHER.
3. CARE SHALL BE TAKEN TO AVOID CONTAMINATION OF THE GEOTEXTILE DURING CONSTRUCTION. CONTAMINATED GEOTEXTILE SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. DAMAGED GEOTEXTILE SHALL BE REMOVED OR REPAIRED AS DIRECTED BY THE ENGINEER AT NO COST TO THE OWNER A GEOTEXTILE PATCH MAY BE PLACED OVER DAMAGED AREAS IF APPROVED BY THE ENGINEER. THE PATCH SHALL EXTEND 3 FT. BEYOND THE PERIMETER OF THE TEAR OR DAMAGE.
4. GRAVEL AND RIP RAP: GRAVEL AND RIP RAP PLACEMENT SHALL BEGIN AT THE TOE AND PROCEED UP THE SLOPE. RIP RAP SHALL NOT BE DROPPED ONTO THE GEOTEXTILE FROM A HEIGHT OF MORE THAN 1 FT. GRAVEL SHALL NOT BE DROPPED ONTO THE GEOTEXTILE FROM A HEIGHT EXCEEDING 3 FT. ANY GEOTEXTILE DAMAGED DURING PLACEMENT OF RIP RAP OR GRAVEL SHALL BE REPLACED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE. IN UNDERWATER APPLICATIONS, THE GEOTEXTILE AND REQUIRED THICKNESS OF RIP RAP SHALL BE PLACED THE SAME DAY.

A circular professional engineer seal for the State of New Hampshire. The outer ring contains the text "STATE OF NEW HAMPSHIRE" at the top and "PROFESSIONAL ENGINEER - B.S." at the bottom. The center of the seal contains the name "BRIAN S. SAKIDVICH" and the license number "No. 14328". The word "LICENSED" is written in a semi-circle below the name. The seal is crossed out with several large, dark, diagonal scribbles.

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

1	ISSUED FOR PERMITTING	10/1/15	FP	RLR	BSS
2	REVISION	DATE	DRWN	CHKD	APPRY
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

Transmission
Business

#

TRANSITION STATION #5
CONSTRUCTION DETAILS

DES: LMP	CHK:RLR
DRW: FP	APR: BSS
TOWN:	
BETHLEHEM, NH	

MILE NO:
SHEET 16 OF 18

NPTT816-C507

